

# BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

## SCHEDULE-B

**NAME OF WORK:** Reserve Fund for Emergency Works in Dasarahalli ward No:15  
(Improvements the prayer Ground to Govt.High School near KalahastiNagara in Dasarahalli ward No:15)


| Sl. No | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Unit | Qty                         | Sanctioned Estimate Rates |                                                                        |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-----------------------------|---------------------------|------------------------------------------------------------------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |                             | In Figures (Rs.)          | In Words (Rs.)                                                         |
| 1      | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 3    | 4                           | 5                         | 6                                                                      |
| 1      | Earthwork excavation for foundation of buildings, water supply, sanitary, lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Cum  | 303.99<br><del>198.99</del> | 288.36                    | Rupees Two Hundred Eighty Eight and Thirty Six Paise Only              |
| 2      | Providing and filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. Complete as per specification and direction of Engineer-in-charge of the work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Cum  | 132.66                      | 2161.08                   | Rupees Two Thousand One Hundred Sixty One and Eight Paise Only         |
| 3      | Providing and laying in position plain cement concrete of mix 1:3:6 with OPC Cement @220 kgs with 20 mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @0.56 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well comated, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Cum  | 66.33                       | 5491.80                   | Rupees Five Thousand Four Hundred Ninety One and Eighty Paise Only     |
| 4      | Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement design mix M30 at 360 kg per cum, with 25mm and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates @ 0.46 cum with superplastizer at 3lts conforming to IS 9103-1999 reaffirmed 2008. coarse and fine aggregate conforming to IS:383, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing, compound, finishing to lines and grades as per drawing Complete as per specification and direction of Engineer-in-charge of the work. | Cum  | 66.33                       | 6943.32                   | Rupees Six Thousand Nine Hundred Forty Three and Thirty Two Paise Only |

Signature of the Contractor  
**EXECUTIVE ENGINEER-4**  
KRIDL, BBMP DIVISION  
BENGALURU-560 010

Executive Engineer

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |     |                             |          |                                                                     |
|---|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|-----------------------------|----------|---------------------------------------------------------------------|
| 5 | Providing T.M.T. steel reinforcement for R.C.C. work including straightening cutting, bending, hooking, placing in position, lapping and (or welding wherever required, trying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per specification and direction of Engineer-in-charge of the work. | Kgs | 2.32                        | 70509.96 | Rupees Seventy Thousand Five Hundred Nine and Ninety Six Paise Only |
| 6 | Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work.                                                    | Cum | 303.99<br><del>198.99</del> | 84.50    | Rupees Eighty Four and Fifty Paise Only                             |

  
 EXECUTIVE ENGINEER-4  
 KRIDL, BBMP DIVISION  
 BANGALURU-560020  
 Signature of the Contractor

  
 Executive Engineer,  
 Dasarahalli Division,